



KERALA HYDEL TOURISM CENTRE

(A VENTURE OF KSEB LTD.)

CABIN NO: 426, 4th FLOOR, VYDHUTHI BHAVANAM, PATTOM,
THIRUVANANTHAPURAM-695 004.

Phone – 0471 2553640, 2514209, 2514457

E-mail - dirkhtc@kseb.in

No : KHTC/HQ/DB2/2018-19

Dated 28.12.2018

QUOTATION NOTICE

No: 11/KHTC/HQ-Qtn/2018-19

***Name of work : KHTC –Munnar – Installation of 62.5 KVA DG Set at
Munnar Hydel tourism Centre.***

Sealed competitive quotations are invited from the experienced contractors for the ***Installation of 62.5 KVA DG Set at Hydel tourism Centre, Munnar.*** Schedule will be issued from the office of the undersigned during the working hours or can be downloaded from website www.hydel tourism.com from 29.12.2018 to 02.01.2018 (1.00 PM). Completed tender forms shall be submitted to this office by registered post / speed post / direct.

The quotation should be submitted before 3.00 PM on 07.01.2018 and will be opened at 3.30 PM on same day. KHTC reserves to accept or reject any quotation without assigning a reason.

Contact : Phone :- 0471-2553640, 9447291220

DIRECTOR
Kerala Hydel Tourism Centre

Copy to :-

1. Spl Officer & TC Member



KERALA HYDEL TOURISM CENTRE

(A VENTURE OF KSEB LTD.)

CABIN NO: 426, 4th FLOOR, VYDHUTHI BHAVANAM, PATTOM,
THIRUVANANTHAPURAM-695 004.

Phone – 0471 2553640, 2514209, 2514457

E-mail - dirkhtc@kseb.in

QUOTATION SCHEDULE

Sl. No:	Specifications	Quoted Rate	Amount
1	Unloading of DG set & its union charge		
2	Foundation Work for providing DG set.		
3	Supply and Laying of 3.5 X 95 Sqmm PVC AL UG Cable upto the change over switch.		
4	Supply and Laying 10 SWG copper wire for Earthing		
5	Termination of the above UG Cable.		
6	Supply and laying of 3.5 X 35 sqmm PVC AL UG Cable upto the change over switch.		
7	Supply and laying of 25 X 3 copper strip for earthing.		
8	Providing 2.5 m long G.I. Pipe Earth stations as per standards.		
9	Supply and fitting 63 A change over switch.		
10	3 out 100 A including suitable metal box and 100 A2 out GSB.		
11	Documentation, preparation and getting approval from Electrical Inspectorate.		
12	DG start stop switch with 2.5 X 4 Core cable		
13	MS cable tray for river crossing.		
14	Inspection fee, security fee etc.		
GRAND TOTAL (Including GST)			

Name & Address of Quotationer

Sd/-

**DIRECTOR
KHTC**